

Union County, Georgia

ADDENDUM # 1

March 25, 2024

Union County RFB Asphalt Resurfacing – Multiple Roads

This addendum is issued to change or clarify the proposal documents associated with the
Union County RFB for Asphalt Resurfacing – Multiple Roads
Issued March 6, 2024

List of Items Included in Addendum #2

1. Questions and Answers (attached)
2. Corrected Appendix D – Bidder's Pricing Proposal

**Note: A signed acknowledgement of this addendum must be received by the
Purchasing Agent attached to your response.**

Vendor Name: _____

Address: _____

Email: _____

Authorized Signature: _____ Date: _____

Name (Printed): _____ Title: _____

Question 1:

What are the work hours for this project?

Answer to Question 1:

No restrictions for the resurfacing of county roads. However, disruption to businesses must be kept as minimal as possible when scheduling the work. Therefore, some work may need to occur after normal business hours.

Question 2:

What are the milling cover up requirements?

Answer to Question 2:

The adjacent businesses must be taken into consideration while completing the milling and interim clean up before final resurfacing.

Question 3:

On page 18 in the bid tab for “9.5 mm Superpave Type II, GP 2 Asphalt with 1-1/2 inch Layer Thickness”, the unit of measurement is in SY. Should this be paid for by the ton?

Answer to Question 3:

Yes, use the line item from this addendum (see below)

Question 4:

Should the 2021 GDOT Specifications be used for this bid?

Answer to Question 4:

No, for purposes of this bid use the spec year as prescribed in the bid documents.

Corrected -- Appendix D
BIDDER'S PRICING PROPOSAL

Spring Creek Road – All (0.8 mi)
 Lance Crossing – Moccasin Road to Spring Creek Road (0.15 mi)
 Fisher Field Road – All (0.66 mi)
 Ivy Log Creek Road – Gum Log Road to Ivy Log Gap Road (0.81 mi)
 Gaddistown Road – Hwy 60 to Marked Area (2.0 mi)
 Old Smokey Road – All (1.18 mi)
 Ivy Log Road – Henson Road to Ivy Log Creek Box Culvert (1.1 mi)
 Loving Road – Mull Road to County Line (1 mi)
 Darby Lane – All (.78 mi)
 Wilson Mountain Road – All (.5 mi)
 Fairview Church Road – Mulky Gap Road to Duncan Cemetery (.67 mi)
 Weaver Road – All (.91 mi)

Proposal Line Number	Pay – Item	Description	Estimated Units	Unit Price	Bid Amount
0010	150-1000	Traffic Control	Lump Sum		
0020	402-3102 Main	Recycled Asph Conc 9.5 MM Superpave, Type II, GP 2 Incl Bitum Material 165 lbs/sqyd	10200 TN		
0022	402-3102 Driveway Aprons	Recycled Asph Conc 9.5 MM Superpave, Type II, GP 2 Incl Bitum Material 330 lbs/sqyd	1725 TN		
0023	402-3100 Leveling	Recycled Asph Conc 9.5 MM Superpave, Type I, GP 1 or Blend 1 Incl Bitum Material 55 lbs/sqyd	2380 TN		
0024	402-3111 Widening	Recycled Asph Conc 19 MM Superpave, Type II, GP 2 Incl Bitum Material 550 lbs/sqyd	345 TN		
0025	413-1000	Bitum Tack Coat	12670 GL		
0035	652-2501	Solid Traffic Stripe, 5 in, White	15 LM		
0040	652-2502	Solid Traffic Stripe, 5 in, Yellow	17 LM		
0045	652-5701 Stop Bars	Solid Traffic Stripe, 24 in, White	312 LF		
			Total Bid Amount		

NOTE: All driveway aprons and intersection tie-ins must be completed before the main travel way.

City of Blairsville - Cleveland Street Phase II

GDOT Pay Item	Description	Quantity	Unit	Unit Cost	Total Cost	Notes
151-1000	Mobilization	1.0	LS			
150-1000	Traffic Control	1.0	LS			
210-0100	Grading Complete	1.0	LS			
432-0206	Mill Asph Conc 1 1/2 Inch	2930.0	SY			
610-9001	Remove Signage	18.0	EA			Salvage for Reuse
	Remove Storm Sewer Structure	3.0	EA			Inlets Only, Storm Structure to be salvaged
610-0012	Remove Sidewalk	615.0	SY			
610-0340	Remove Existing Curb	840.0	LF			
610-2730	Remove Rigid & Flexible Pavements	425.0	SY			
	Saw Cut Rigid & Flexible Pavements	3000.0	LF			
610-6605	Remove Existing Light Poles	2.0	EA			Salvage for Reuse
402-3102	Recycled Asph Conc 9.5 MM Superpave, Type II, GP 2 Incl Bitum Material 165 lbs/sqyd	250	TN			
413-1000	Bitum Tack Coat	348.0	GL			
	Speed Tables	18.0	CY	OMIT	OMIT	To Include Reinforcement Dowels
441-6012	Conc Curb & Gutter, 6in x 24in x 12in	815.0	LF			
	Conc Curb & Gutter, Recessed	508.0	LF			

441-4020	6" Conc Valley Gutter/Conc Pavement	505.0	SY			
441-0104	Conc Sidewalk, 4 Inch	380.7	SY			
636-1036	Install Signage	18.0	EA			Use Salvaged Signage
	Install Light Poles	2.0	EA			Use Salvaged Light Poles
653-1501	Thermoplastic Solid Traf Stripe, 5 in, White	1400.0	LF			5" White Edge Line & Parking Strip
653-1804	Thermoplastic Solid Traf Stripe, 8 in, White	290.0	LF			8" White Solid Edge Line
653-1504	Thermoplastic Solid Traf Stripe, 12 in, White	30.0	LF			12" White Hatching
352-3502	Thermoplastic Skip Traf Stripe, 5 in, Yellow	190.0	LF			5" Yellow Skip
653-1502	Thermoplastic Solid Traf Stripe, 5 in, Yellow	1720.0	LF			5" Yellow Solid
653-6006	Thermoplastic Solid Traf Stripe, 8 in, Yellow	50.0	LF			8" Yellow Solid
653-6006	Thermoplastic Traf Stripping, 12 in, Yellow	120.0	LF			12" Yellow Solid
653-0120	Thermoplastic Pvmt Marking, Arrows	1.0	EA			Type 1 & Type 2
668-2100	Precast HGI Drop Inlet	1.0	EA			Adjust & Install 1019A-TP E
668-2101	Precast HGI Drop Inlet	1.0	EA			New Doghouse Manhole w/ 1019A- TP E
668-1100	Concrete Catch Basin, GP 1	2.0	EA			Adjust & Install, 1034 D
	Mulch	1.0	AC			Ds1
163-0232	Temporary Grassing	1.0	AC			Ds2
700-6910	Permanent Grassing	1.0	LS			Ds3, Ds4 & Fertilizer
163-0300	Construction Exit	1.0	EA			Co

163-0550	Construct and Remove Inlet Sediment Trap	3.0	EA			Sd2-F
171-0010	Temporary Silt Fence, Type A	500.0	LF			Sd1-NS
				<i>TOTAL ESTIMATED CONSTRUCTION COST</i>		

Name & Title of Person Authorized to Sign

Name

SIGNATURE

Title